

Stonemill Creek Fire Department  
Bid Specifications  
Bid #1819-20

SUMMARY OF PROJECT

- Bid packet must include the following:  
Copy of Florida DBPR license  
Copy of General liability insurance  
Copy of Florida workmans Comp. insurance  
ALL INSURANCE NEED TO BE CERTIFIED TO GULF COUNTY BUILDING DEPARTMENT.
  
- Licensed Contractor must Order an 80 x 75 Metal Building with miscellaneous supplies, designed to meet F.B.C 2017 and 130 MPH wind with 4" min. reinforced insulation walls and roof with foundation and erect building.  
5—14x16 manual roll-up doors  
4—30/68 exterior fire rated doors  
2 - 30/68 interior fire rated doors  
5 – 30/40 windows  
**Gulf County BOCC will direct purchase from this vendor to save money on TAX**

SCOPE OF WORK

- Construct a concrete building pad per FBC 2017 and engineer 6" slab under bays and 4" slab underneath other areas. Supply all material except concrete.  
**Gulf County BOCC will direct purchase from the CONCRETE vendor to save money on TAX. Estimated 200 yards \$25,000.00**
  
- Install all rough plumbing in slab per plans
- Install all underground electric needed in slab per plan and unground piping for outside lights
- Erect building per plans
- Construct 2-hour fire rated wall partition per plans approximately 96 linear ft. using 3 5/8" metal studs spaced on 16" O.C. with 2 layers of 5/8 type X Gypsum board on each side and staggered joint, with sound barrier insulation between. Extending to the roof deck. Exterior joints must be sanded and finish.  
No Paint
  
- **Alternate bid**
- Install 200-amp meter base with disconnect NEMA 3R
- Construct 20x20 concrete handicap parking pad with signage.
- Install potable well pump with minimum 30 GPM, 2" discharge, 200 gallon galvanized tank and all controls for 230 volts. Deep well casing as already been installed.